



Existing Lisacorn floor slabs to be taken up and stored on site for removal by client. Concrete floor to be cleaned and prepared to take new tiles in reception area as per spec, new carpet in interview rooms and new marmoleum finish to associated corridor as per spec. Include for floor levelling compound. NOTE: Existing perimeter skirting board to be removed and replaced with new skirting as per spec. Refer to Drg. No. 3215-T-1.3 for floor finishes plan

Existing double door to be removed. Make good to all junctions and repaint locally

Remove existing timber screen and fit new fire rated screen as per door schedule. New fire rated bulkhead partition over new screen.

Existing store to be removed. see electrical drawings for removal of any services in this area. make good to floor and wall junctions

All existing walls and proposed new walls to Reception, Existing WC, Interview Rooms and associated corridor to be repainted. New joinery in these areas as per spec. Refer to Drg. No. 3215-T-1.1 for painting & decorating spec and layout for walls and joinery

New partitions to interview rooms to be erected off existing concrete slab in positions as shown. New 138mm Gyproc GyproWall partition wall or equivalent approved up to underside plasterlab ceiling over 200mm of Cypframe 70/550 'C' studs @ 600mm centres. 22.5mm floor & ceiling channel and 32mm ball joint bar to one side only. 40mm of 12.5mm Gyproc Soundbloc plasterboard each side and 50mm Moy Acoustic Roll in the cavity. Partitions to be skimmed and painted both sides. Partitions to achieve a 60min fire rating and a sound reduction of 25dB. Partitions to be created over interview room grooves. Existing partitions carried up to underside of concrete floor and repainted.

EXISTING RECEPTION/ MAIN ENTRANCE
New manifestations to glazing in accordance with TGD Part M 2010. (see note below)

EXISTING SECURE LOBBY

Refer to drg. no. 3215-T-6.2 for reception desk details

Remove existing ceiling tiles and grid to entire reception area. Fit new ceiling grid and tiles to spec to area highlighted in reflective ceiling plan. Fit new plasterboard ceiling with a painted skim finish to remainder of ceiling. Existing Interview Rooms. Raised section of ceiling in main reception area. Refer to Drg. No. 3215-T-1.1 for reflective ceiling plan for new ceiling layout. Refer to M&E drawings and spec for new layout

Refer to drg. no. 3215-T-6.2 for reception desk details

